Welcome! Thank you for choosing the HiQ Solar 480V TrueString Inverter. Set up is easy....

What's in the box?

You'll need most of the following. For some items we will send you one per shipment to save waste



TrueString Inverter TS480-8k



PV Connector Tool

AC Cable - ordered separately, CBL-480A-05 (5') CBL-480A-15 (15') CBL-480A-30 (30') CBL-480A-50 (50')



AC Splice, ACSPL-60 (optional)



Gateway (GW-A-277) with included SD Card, Ethernet cable


Included 277V Gateway AC cable




Warnings

- System to be connected to 480V 3-phase Wve (3 phases, neutral, ground) ONLY
- No user-servicable parts inside tampering with the unit will void the warranty
- Applying the incorrect polarity to DC string inputs will result in damage and void the warranty
- Communications Gateway is for indoor use only

Line



• All 5 circuits (L1, L2, L3, Neutral, Ground) must be connected and Neutral must be bonded to earth ground. Failure to do so can damage the unit and void the warranty



Notes on siting

- NEMA6 rated
- May be placed almost anywhere
- Cooling most efficient if unit is mounted vertically in shade, bolted to racking, with connectors pointing downwards. However, any orientation is acceptable
- Mounting hardware up to 5/16" will fit the baseplate mounting slots.

Grounding

- Metal enclosure must be grounded (NEC 690.43)
- Equipment ground achieved through AC connector
- Optionally, grounding may be achieved by adding a lay-in lug (not provided) or through mounting bolts to a grounded metal structure using

paint-cutting washers

Connect to Grid

480V

only

3-phase

Remove sealing cap Connect inverter AC cable to the AC system. Connector is certified means of AC disconnect

Any color to any phase

White to Neutral Green to Equipment Ground

Mate AC connector receptacles. Unit is only watertight when all connectors fully engaged

(Unmating requires tool - insert center pin into hole in connector collar and turn assembly)

Optional AC Splice

HiQ Solar ACSPL-60 may be used to combine up to 3 TrueString inverters to one dedicated branch circuit



Dedicated branch circuit. 60A OCPD max AC Cables of up to 3 TrueString inverters

Connect **Gateway**

Using Gateway AC cable, make connections to one phase through 15A OCPD, as close to PV array as possible



Site Gateway indoors. Ethernet network connection may be made now.






Nearly there! Finishing up.....

Discover **System**

- Switch on AC power to the Gateway and the inverter(s)
- Press 'Discover' button
- Gateway will search for any/all TrueString inverters and check they are healthy
- Press 'Detail' button. If a fault is indicated, check AC wiring



• Switch AC back on if necessary

Inverters Gateway

Power On

Off+Unlock

Off+Lock

Clear Fault

generating power.

• The system will wait 5 minutes, self-test then start

Connect **PV Strings**

Instructions

- Optionally, switch off AC to inverter
- Remove connector end caps
- Connect 2 strings
- Secure DC wiring to array racking Design
- 1,000V-rated
- String lengths, stacking etc. see installation manual
- Uneven strings are ok, see manual
- Connectors are certified means of DC disconnect, don't need additional disconnects

Warning

 Do not reverse + and - polarities on DC inputs, this will damage unit and invalidate warranty



If no AC. button flashes red - normal at this stage

Buttons & Indicators


More information and other indications detailed in the installation manual

	30/0
Button State	Meaning
DISCOVER	Initial state
DISCOVER	Once pressed, in process of discovering inverters. Will return to initial state with empty serial number list if no inverters found
DISCOVER	 Error found, for example signal strength too low, too much background noise on circuit. Red color only clears when user re- tries & fault condition no longer applies
DISCOVER	Once discovery has successfully occurred, button returns to original state

Mate DC connector receptacles. Unit is only watertight when all connectors fully engaged



Unmating requires included tool as shown



Left-right flash

Inverter

Button Push

2 presses

3 presses

Meaning

1 press • Make inverter beep

("are you alive?")

• "Off & locked" - disabled

Do not 5-minute self-start

Start generating immediately

If locked, unlock & generate

Powered up

Not generating

immediately

No faults

• Power-on self-test (will take <1 minute)

Green chaser

Powered up

Generating

No faults

Rapid flashing • Faulted. For example, arc detected

Mostly on

• "Off & locked" - disabled

Mostly off

Sleeping - not generating

Gateway Indications:

Array Summary

Array

- Gateway's AC wiring is correct (Neutral is connected, voltage is within tolerance)
- The SD card is inserted and the file system is OK

SD NET HIQ

1/1 Inverters Visible

1 Locked Off

0 W / 246445.5 kWh

- NET • The network is connected. Ethernet cable is OK, Gateway has acquired an I.P. address
- HIO Gateway was able to contact the HiQ server and upload data

- Press 'Array' button on Gateway
- Pressing 'Off+Unlock' button will unlock any previously locked inverters
- Press 'Power On' to omit the 5 minute delay if desired
- Gateway communication health is shown



TrueString Inverter











You're

Congratulations. More information at www.higsolar.com.



